

WASHING ACCESSORIES

Increase Your Pressure Washing Speed with Accessories



 **HYDROTEK**

ROTARY SURFACE CLEANERS




- driveways, drive-thrus
- patios, garages
- concrete sidewalks
- school yards
- factory & warehouse
- restroom floors
- food processing floors
- service stations
- concrete parking lots
- pool decks
- sport courts
- roofs & decks
- loading docks
- tile flooring
- stadiums
- marina docks
- moss & mildew removal

Hydro Twisters® are industrial flat-surface cleaners that connect to a pressure washer and use a spray bar rotating at a high speed just above the ground to clean concrete more consistently and faster than an operator with a wand, with less fatigue. A surface cleaner uses much less water than a hose wash down. Hydro Twister surface cleaners can be used with cold water or up to 250°F hot water, on some models, for extra stubborn grease or grime, eliminating the need for soap pretreatment in most applications.

The Hydro Twister® Advantage...

- Low Profile Deck: Will fit under benches & machinery
- Less Fatigue: Handle is mounted at an ideal working angle
- Hose is protected inside stainless steel handle (except hoop handles)
- Rustproof, stainless deck / handle and heavy duty for daily use
- Brush guard to reduce splash on building windows and operator

The **TRIDENT HYDRO TWISTERS®** clean more square footage than others in their class. The proprietary aluminum spray arm with compound angled nozzles not only clean up to the edge but also push water aside to create more impact on the surface they clean. All stainless, rustproof deck and handle construction will keep your surface cleaner working and looking great for years.



Trident Hydro Twisters come in two deck sizes, 24" and 28", and your choice of mobility.

Choose the caster version with three non-marking casters that allow the operator to freely move side to side or forward. Handle is free floating and folds flat for storage. The high pressure hose is protected inside the stainless handle tubing, ready for you to connect the pressure washer trigger gun.

If you are looking for a pressure adjustment feature to wash more delicate surfaces or are cleaning large areas, choose the fixed rear wheel option. A front non-marking caster paired with two large, airless tires reduce fatigue when working in straight lines. Dial up or down the pressure as needed from the hoop handle which folds down for carrying or storage.


Models: Choose your deck size and mobility

- 24" deck, 2 nozzles on spray arm, 3 casters
Model# ANT24
- 28" deck, high flow swivel, 4 nozzle spray bar with optimized thrust angle, 3 casters
Model# ANT28
- 24" deck, 2 nozzles on spray arm, two airless rear wheels with hoop handle
Model# ANT25
- 28" deck, high flow swivel, 4 nozzle spray bar with optimized thrust angle, two airless rear wheels with hoop handle
Model# ANT29



The **CONTRACTOR HYDRO TWISTER®** is the proven choice for professional surface cleaning...with four tools for your cleaning needs. The Contractor Twister combines a rotary surface cleaner, spot / gum remover, hydro broom, and an edger to create an all-in-one deluxe surface cleaner. The dual trigger guns activate either the rotary spray arm or one of the other three on-board tools. By combining four processes into one unit, you will save time and fatigue when cleaning large expanses of concrete, parking lots or other flat surfaces. The secret that makes the Contractor Hydro Twister so effective is the ideal water spray angles and nozzle heights that optimize cleaning power. Model# ANT4C

An onboard edging tool cleans close to planters, columns, and walls or use the water broom to rinse a large area



The under-deck spot remover uses a "six-shooter" nozzle to blast away gum or paint.

Caster pivot lock allows the operator to choose to lock casters for use in straight lines or unlock for cleaning side-to-side.



Choose the Hydro Twister with the deck and nozzle size that accommodates your pressure washer

	ANT24	ANT25	ANT29	ANT28	ANT4C
Max. recommended psi	5000	4000	4000	4000	4000
Max. flow (w/larger nozzle)	6	6	10	10	10
Min. recommendations	3000psi / 3gpm	3000psi / 3gpm	5.5 gpm	5.5 gpm	5.5 gpm
Standard nozzles (15°)	2) #2.7	2) #2.7	2)ea #1 & #2	2)ea #1 & #2	2)ea #1 & #2
Water temperature	cold to 210°F	cold to 210°F	cold to 250°F	cold to 250°F	cold to 250°F
Deck size	24"	24"	28"	28"	28"
Other	High flow, high temperature swivel				
Deck construction	Round stainless deck, brush splash guard			Stainless octagon, brush splash guard	
Handle/frame construction	Stainless, wishbone	Stainless, hoop handle, w/adjustable pressure valve		Stainless, wishbone handle, trigger gun (dual guns on ANT4C)	
Wheel style	3 non-marking casters	1 caster & 2 airless rear tires	3 non-marking casters	4 non-marking casters	

WATER RECOVERY SURFACE CLEANERS



The Twister Vac is a unique rotary surface cleaner with wash water recovery capability. Imagine how efficient you will clean without the hassle of having to do a final rinse or containing wastewater runoff. Using a Twister Vac with your existing hot water mobile wash skid, you will be able to clean flat surfaces up to 20,000 sq. ft. per hour, plus recover your wash water all in one simple step when you connect to a Hydro Vacuum® recovery system.

Stainless construction, 30" deck with brush splash guard. Requires minimum 100cfm/91"lift vacuum source, 2" vacuum hose, and a pressure washer. Suitable for use on greasy factory floors, concrete parking lots and drive-thru areas, gas stations and garages. Model# ANTV5



4000 / 5.5 Max. recommended psi/flow
6 gpm Max. flow (w/larger nozzle)
3000 / 4.8 Min. recommended psi/flow
2) #2.7 nozzles, 15°
cold to 200°F
30" deck (22" cleaning path)
Stainless octagon deck, brush splash guard, floating handle, trigger gun, 4 non-marking casters

For additional Mobile Wastewater Solutions, ask your dealer for the Hydro Vacuum® product line.


HOSE REELS



Stainless steel for the price of painted steel.

The Hydro Tek hose reels are made with rust-proof stainless & zinc plated steel to withstand harsh environments.

Part #	Max. Temp.	Capacity	Max. PSI	Type
AR100	250°F	150' of 3/8"	3500	narrow-base mount, friction brake
AR150	400°F	150' of 5/8"	5000	narrow-base mount, friction brake
AR110	250°F	250' of 3/8"	3500	large-base mount, pop-pin brake
AR151	400°F	250' of 5/8"	5000	large-base mount, pop-pin brake
AR152	cold	150' of 5/8"	inlet	large-base mount, pop-pin brake
AR188	400°F	5000	wall mount to 16" stud width	



AR188

If you are looking for a **wall mount hose reel** or a **base mount reel** for mounting almost anywhere, Hydro Tek universal mount reels are right for you. These reels are shipped fully assembled, ship quick, and are proudly made in the USA



AR110, AR151, AR152 (approx:16"lx19"wx18"h) AR100, AR150 (approx:16"lx13"wx18"h)



Hose & gun sold separately

Need a **pivoting hose reel**? Look at the AR425. The stainless reel has a capacity of 150' x 3/8", 5000psi, 400° and is designed to mount on tubing with the enclosed clamp, or can be mounted on a wall. The reel has a friction brake for adjusting the drag depending on your job. It will pivot a full 360 degrees or you can slide the pin to lock the rotation where needed.

Stacking Hose Reels

Two stainless hose reels attached to a sturdy powder coated steel frame that conveniently bolts down to any flat surface. Ships in two boxes, ships quick & made in the USA

Two configurations to choose from: Part# AR325 has reel capacities of 250' x 3/8", 5000psi, 400° paired with a 150' inlet reel.

Part# AR326 has reel capacities of 250' x 3/8", 5000psi, 400° paired with another of the same.

HOSES

Smooth rubber pressure washer hose with M22 screw couplings and bend protectors. Max 3000psi and 140°F. For use with homeowner/consumer/light duty pressure washers. 50' x 1/4" Part# DH426



Heavy duty, silicone-free **inlet garden hose** with heavy duty brass fittings on both ends. 100' x 5/8" Part# AG100



The 3/8" **high pressure hoses** are available in 3000psi, 4000psi, and 6000psi, lengths of 50' or 100' and include bend protectors and couplers.

Part #	Temp.	Length	psi
DH050	250°F	50'	3000
DH095	250°F	100'	3000
DH057	250°F	50'	4000
DH097	250°F	100'	4000
DH060	250°F	50' non-marking double wire braid	6000
DH098	250°F	100' non-marking double wire braid	6000

BULK TANKS


Hydro Tek's custom **bulk water tanks** are made from seamless linear polyethylene. Tanks include a large 10" fill lid. The 200 gallon tank is self supporting, while cages or strapping are recommended on larger tanks to keep shape when full. Tanks are available in black or white. You won't need to create a tie down strap, we've done it already. The Hydro Tek steel hold down straps are fabricated to fit these tanks securely. Simply bolt straps down to your flat trailer. Two straps required per tank.

TANKS

Part# WT069, 70g, black (48"x25"x13")
Part# WT201, 200g, white (48"x29"x34")
Part# WT202, 200g, black (48"x29"x34")
Part# WT265, 270g, white (48"x34"x41")
Part# WT267, 270g, black (48"x34"x41")

HOLD DOWN STRAPS

Part# HCS20, for 200g tank, stainless
Part# HTS34, for 270g tank, stainless
Part# HTS35, holds two 270g tanks



SPOT FREE



Connect this **DI water filter cart** to your existing cold water power washer (up to 3gpm) for spot free washing or connect to a low pressure hose for low flow, unpressurized spot free rinsing. More compact and portable than others on the market, a stainless steel frame encloses and protects the built-in filter housings. Simply insert a Hydro Tek filter pack to remove the impurities from tap water for a spot free finish without having to dry the surface. Quick read meter monitors the water quality to let you know when it is time to change the filters. System designed to conserve water flow and increase filter life.

Model# CWD00

The Hydro Tek Spot Free Advantage...

- On-demand DI water: no more bottle leases, bulky bottle storage, or running out of pre-purchased DI water
- Ideal for auto, RV, boat, bus, truck, or window washing.
- Hydro Tek DI filter packs have a high yield and produce ultra pure water. (Treats up to 1000 gallons to a purity of 5ppm or better in average tests, when inlet TDS is 150ppm or less)

HOT WATER GENERATORS

Do you already own a cold water pressure washer but wish it had hot water? Attach a **Hot Link** to your existing cold water pressure washer and you have the power of hot water to quickly melt away grease and grime.

The Hot Link system allows you the flexibility of using hot water on those stubborn jobs such as grease, gum, or graffiti that require the impact of hot water to get the job done right. It will save you money by getting the job done faster, and you do not have to buy a new pressure washer if you already have a cold water system. Its compact size allows for easy storage when not in use and takes up little room on your truck or trailer.

You can choose from two diesel heated, electric powered models.

- 12v DC for remote use, hook to the battery on your pressure washer (requires 14 amp charging system)
Part# CPHL5DC
- 115v, plugs into any standard 15 amp outlet
Part# CPHL5E1




WANDS & SPECIALTY APPLICATIONS

Heavy duty **spray wands** include insulated lance grips for both protection from heat and comfortable two handed use.



Part# AVW40, 42" stainless steel dual lance wand
 Part# AVWA3, 42" stainless steel dual lance wand with gun and coupler
 Adjustable pressure at the wand or use for downstream soap applications.
 Includes soap nozzle

Part# AVGH2, 48" spray wand with coupler and trigger gun



Convenient nozzle storage at your fingertips
 Part# AVGH3, 48" spray wand, coupler, trigger gun, nozzle holder



Need to pressure wash up high? Reach it safely from the ground with Hydro Tek's **High Reach Wash Pole**. It offers additional control and rigidity not found with telescopic wands. Uses trigger gun from your wash skid, no need to turn off wash skid or change guns. Our maximum ratings are 4500psi and 250°F (while other brands are rated only to 195°F). The Hydro Tek high reach wash pole includes a comfort brace gun holder, full length jumper hose, three sections of 6' poles, spray head attachment, and also includes shoulder strap (Gun holder will hold Hydro Tek VG200 and Suttner ST1500 trigger guns.) Part# AVW20, High Reach Wash Pole



No need to turn off pressure washer to change wands! Hydro Tek washer gun (or Suttner ST1500) snaps easily into gun bracket.



Clean the undercarriage of trucks, boats, and farm equipment with the **Undercarriage Washer**. Attach this accessory to a hot or cold pressure washer (up to 210°F) to effortlessly remove grime from the underside of vehicles and equipment. If you need to clean concrete, simply reverse the casters and flip the deck over to be used as an efficient flat surface cleaner. Rust resistant, stainless steel construction, with an aluminum spray bar, to ensure a long life of use even in corrosive environments. 24" deck width, 7" clearance height needed, max 5000psi, 6gpm Part# ANTUN


For removing dirt and grime from underneath a vehicle, reach for a Hydro Tek **undercarriage wand** with casters (#AVUN1). Simply attach the wand to your power washer gun, insert your quick connect nozzle and roll under vehicle. The undercarriage wand is also ideal for cleaning under boat trailers and motor homes. Part# AVUN1



Looking for an industrial **chemical sprayer / tank system**? The Hydro Tek low pressure chemical sprayer runs off a 12v battery or can be wired directly to a Hydro Tek wash skid battery and has lighted on/off switch. The rugged frame can be mounted to your existing flat trailer or truckbed, or factory installed on your new ProTowWash® trailer. Includes 50' braided chemical hose, spray wand and 40 gallon chemical tank. Part# AC440



To blast off paint, rust, scale, or graffiti try **wet sandblasting**. The Wet Sandblast nozzle draws sand or even baking soda into the water stream. The standard sandblast assembly features an industrial sand blast head, 50' crush proof PVC sand hose, and a sand probe that will draw directly out of a bag or pail (#ASB55 has 5.5 nozzle size, other sizes available). Baking soda can be used for more delicate jobs such as pool tile cleaning and other sensitive surfaces.



SPECIALTY SPRAYING SYSTEMS

The **Low Impact, High Reach Spraying System** is a soft wash system ideal for cleaning surfaces that are not tolerant to the impact of a high pressure washer. Simply drop the chemical hose into your tank of solution, even Chlorine, and you are ready to go. Reach rooftops and walls from the ground up to 40' without the use of ladders saving time and increasing worker's safety. It uses two 6 volt batteries and is compact making this a great addition to your wash rig. Includes 250' hose on stainless reel, trigger gun valve and 24" wand. Part# AC110



Need to clean a dirty roof? Attach this **Roof Cleaner** to a hot or cold pressure washer (up to 175°F) to remove algae, mildew, and dirt streaks from a roof. Constructed of rust resistant stainless steel with an aluminum spray bar to ensure a long life of use, even in corrosive environments. Includes a pressure reduction valve, pressure gauge, non-marking wheels, and a ball valve to shut off water. Wheel width and height are adjustable, without tools, for maximum impact on a variety of roof styles. 24" deck width, Max 4000psi, 6gpm Part# ANTR1

WATER RECOVERY ACCESSORIES



Turn your pressure washer into a **sludge, slurry or water evacuation tool**. Pressure energy of spray from pressure washer wand creates suction that pulls water, up to 87gpm, through a heavy wall discharge hose. The Hydro Tek scupper connects to existing 1/4" pressure washer wand quick connect coupler, no other tools required. Ideal for clean out of sump pits, draining a fountain or pond, and flood cleanup. Part# ANS04 or ANS55

▶▶ For a video, scroll down at: <http://www.hydrotek.us/accessories-video/>



Protecting storm drains from wash water run-off is important to mobile wash contractors. Using berms is the simplest way redirect wastewater. To contain and recover the wash water, arrange sand tube berms (available in 2', 6', 10') and place a vacuum scupper attachment or Hydro Vacuum Arch (#ATP40) to vacuum the water run-off.



Hydro Vacuum Arch
Part# ATP40



2' gutter berms,
ZMAT2 & scupper



Scupper, #ZMAT6 10' berm,
& #ZMAT7 6' deluxe berm

WATER & FLOOD RECOVERY VACUUMS

See additional Hydro Vacuum® wastewater solutions products at <http://www.hydrotek.us/water-recycle-and-recovery-systems-video/>



Capture and transfer up to 3000 gallons of water per hour with the compact RPV vacuum system. Features a powerful, industrial 2-stage vacuum motor. A heavy duty, stainless steel pump transfers wastewater up to 100' away while vacuuming continues...no need to stop and dump the collection tank. It is ideal for interior and exterior facilities maintenance contractors who need to collect wash water or for restoration contractors who need to pick up large volumes of water after a fire or flood. Increase your efficiency with optional vacuum tools or even a Twister Vacuum that can be used with Hydro Tek recovery vacuums. (For use with cold water or hot water up to 200°F)

Looking for a high powered dry/shop vacuum? Add the optional dry work filter and vacuum accessories to your RPV and you have an incredibly high powered dry vacuum. Ideal for a building service contractor or a professional auto detailer.

- Model# RPV30E1 - Recover and transfer 30gpm
115v, 15amp or 3500w generator
- Model# RPV50E1 - Recover and transfer 50gpm
115v, 20amp or 5500w generator



Optional portability available: Choose either a caster wheel kit or a dolly style wheel kit

The **Engine Driven Water Vacuum** is a powerful water capture and transfer system. The vacuum/blower is gas engine driven and the transfer pump can be plugged into any Hydro Tek SC or SCU pressure washer generator, no outside power needed! (You can plug into a wall outlet or 2000w generator, too).

Each separation tank has an automatic transfer system which pumps the water out to your bulk tank, landscape, or sanitary sewer where permitted, without loss of suction or lost time dumping tanks. The RGV Hydro Vacuum® is capable of one or two pickup devices, up to 350' total hose length up to 25gpm. It is ideal for facilities maintenance contractors who need to collect wash water or for restoration contractors who need to pick up water after a fire or flood. (For use with cold water or hot water up to 200°F)



- Model# RGV40 - Recover and transfer up to 25gpm from up to 350' of pickup hose
Gas Engine pickup, 115v, 15amp powered transfer (compatible with 2000w or Hydro Tek wash skid generator)

▶▶▶ See most accessories in action at: <http://www.hydrotek.us/accessories-video/>
DISTRIBUTED BY:

HYDRO TEK
CLEANING EQUIPMENT MFG.
2353 Almond Ave. Redlands, CA 92374
phone 800.274.9376 or 1.909.799.9222
www.hydrotek.us fax 909.799.9888